

॥ ओउम् ॥



GEETA DEVI DAV PUBLIC SCHOOL

BHANDARKOLA, SATAR ROAD, DEOGHAR - 814114 (JHARKHAND)

Managed by : DAV College Trust & Management Society, New Delhi - 55

Affiliation No. 3430162
School No. 66358

E-mail : gddavpublicschooldeoghar@gmail.com Website : www.gddavdeoghar.org

Tel No. 9431384841, 9229295878, 9431384840

A Senior Secondary English Medium Co-educational School Affiliated to CBSE, New Delhi

Ref. No. DAV/PG.R/2025-26/734

Date 07/02/2026

'Tender Notice'

We hereby invite a tender for providing and laying of interlocking paver block pavement work at the School Campus.

Note:

Work to be finishes as per the standard and estimate attached herewith.

Interested party may finish the quoted rate with GST and other charges (if any) in a sealed envelope latest by 14/02/2026 through By Hand/Registered /Speed Post.

Sd/-

Principal

Note: - The school may be cancel this tender notice at any time without assigning any reason. If it deems necessary.

BILL OF QUANTITY

Name of Work:-

Providing and Laying of interlocking paver block pavement work at back side of F Block(New Building)Building of Geeta Devi DAV Public School, Bhandarkola, Deoghar-814114, Jharkhand(India).

Statement Of Area :-

1. At Ground Area = 3520sqft = 325.28sqm

Sl. No	Item Description	Qty	Unit	Rate	Amount
1	Earth work in surface excavation by mechanical means Hydraulic excavator/Manual means over areas, not exceeding 30cm in depth but exceeding 1.5m in width as well as 10 sqm on plan)including getting out and disposal of excavated earth lead up to 50m and lift upto 1.5m, as directed by E/I.	104	cum		
2	Material for fixing bedding sand(Screened)or in plinth including ramming & watering in layers not exceeding 150mm thick with all leads(for 25mm Thick & jointing)Laying in position cement of specified grade, All work up to plinth level:1:3:6(1 Cement:3 Coarse Sand(Zone-3):6 Graded Stone Aggregate 20mm nominal size).	104	cum		
3	Providing & Fixing 80mm thick factory made cement concrete interlocking paver having 50N/Sqmm, block of M-30 grade made by block making machine with strong vibratory compaction, of approved size, Design and shape, laid in required colour & pattern over and including 50mm thick compact bed of coarse sand, filling the joints with line sand etc. All complete as per the direction of E/I.	325.28	sqm		
4	Providing and Laying 20mm thick cement concrete 1:3 cement/coarse sand mortar and top finished floating coat of neat cement slurry.	4.05	cum		

5	Labour charge for handling laying of Paver block including sand spreading, Levelling, Compacting & Cutting the edge, etc.	325.28	sqm		
Sub Total					
GST 18%					
Total Cost					
Total Cost In Words					
Submitted By: Contractor Representative: Contractor Seal:		SIGNATURE			